

9. REQUIRED EQUIPMENT & MATERIALS PRICE SCHEDULES

The Contractor shall fill out the unit prices for the services, equipment, and materials listed below. These tables will form the financial basis of the contract.

Table A: Rig Services & Civil Works (Operations)

Item	Description of Equipment & Rig Services	Unit	Quantity	Unit price (SP)	TOTAL price
1	Rig operation rate	day	100		
2	Rig standby rate	day	30		
5	Mobilization/Demobilization fee of the rig and equipment to/from well locations via Lowders (Distance <= 100 km)	trip	4		
6	Mobilization/Demobilization fee of the rig and equipment to/from well locations via Lowders (Distance > 100 km)	trip	1		
7	Civil works: Excavation, hauling, backfilling, and leveling of the rig site from debris of any kind	m³	50		
8	Civil works: Casting and preparation of rig concrete foundations and cable pits, including all necessary materials and supplies Reinforced concrete slab around cellar (250KG) 80kg/1m³ Reinforced concrete slab and walls (350KG) 104Kg/1m³ Cement SRC	m³	100		

Table B: Materials & Equipment

Item	Detailed Equipment & Materials Description	Unit	Quantity	Unit price (USD)/SP	TOTAL price
1	HYDRAULIC SET RETRIVEBLE PRODUCTION PACKER 7" (with Redressing kit items Casing size 7" 29-32 lb/ft Minimum ID 2.5" Top/Bottom Thread 3 1/2" New Vam 9.3 lb/ft	Set	4		
2	HYDRAULIC SET RETRIVEBLE PRODUCTION PACKER 5" (with Redressing kit items Casing size 5" 15-18 lb/ft Minimum ID 42 mm Top/Bottom Thread 3 1/2" New Vam 6.5 lb/ft	Set	1		
3	HYDRAULIC SET RETRIVEBLE PRODUCTION PACKER 9 5/8" (with Redressing kit items) Casing size 9 5/8" Minimum ID 2.5" . Top Thread & Bottom Thread 3 1/5" New Vam 9.3 lb /ft	Set	1		

4	X-mass tree 3 1/8" x 5000, ACC To API specification - 6A (AA' Material CLASS, PSL- 2. PR-2, TEMP CLASS-U) Parveen or equivalent	Set	1		
5	Tubing spool-adapter tubing Hanger (11" x 7 1/6") 5000 psi ACC. TO API specification 6A (AA' Material CLASS, PSL-2, PR-2, TEMP CLASS-U)	Set	2		
6	Casing head 13 5/8" x 5000 psi, ACC. TO API specification – 6A (AA' Material CLASS, PSL-2, PR-2, TEMP CLASS-U)	Set	1		
7	Casing spool 13 5/8" x 11" x 5000 psi, ACC. TO API specification 6A (AA' Material CLASS, PSL-2, PR-2, TEMP CLASS-U)	Set	2		
8	Tubing 3 1/2" New Vam or equivalent 9.3-10.2 lb/ft	Ton	50		
9	Tubing 2 7/8" New Vam or equivalent 6.5 lb/ft	Ton	30		
10	Sodium chloride (Nacl)	Ton	60		
11	Potassium chloride (Kcl)	Ton	10		
12	Bentonite	Ton	15		
13	Fine & Medium Granular (CaCo3).	Ton	75		
14	Soda Ash	Ton	5		
15	CMC (LV& HV)	Ton	5		
16	Caustic Soda	Ton	5		
Estimated total value					

UNSCHEDULED ITEMS NOTE: If any emergency or specialized equipment/materials not listed in the pricing schedules are required to execute the workover program, the Contractor shall submit a separate invoice for these items. Such charges must be backed by a joint minutes of meeting and formally approved by the HPC supervision committee.